



HAL
open science

Overlap Graph for Assembling and Scaffolding Algorithms: Paradigm Review and Implementation Proposals

Victor Epain

► **To cite this version:**

Victor Epain. Overlap Graph for Assembling and Scaffolding Algorithms: Paradigm Review and Implementation Proposals. 2022. hal-03815190v1

HAL Id: hal-03815190

<https://inria.hal.science/hal-03815190v1>

Preprint submitted on 20 Oct 2022 (v1), last revised 26 Oct 2022 (v3)

HAL is a multi-disciplinary open access archive for the deposit and dissemination of scientific research documents, whether they are published or not. The documents may come from teaching and research institutions in France or abroad, or from public or private research centers.

L'archive ouverte pluridisciplinaire **HAL**, est destinée au dépôt et à la diffusion de documents scientifiques de niveau recherche, publiés ou non, émanant des établissements d'enseignement et de recherche français ou étrangers, des laboratoires publics ou privés.

Overlap Graph for Assembling and Scaffolding Algorithms: Paradigm Review and Implementation Proposals

Victor Epain

Univ. Rennes, IRISA/CNRS, Inria, F-35000 Rennes, France

14th October 2022

Abstract

Assembling *Deoxyribonucleic Acid (DNA) fragments* based on their *overlaps* remains the main *assembly* paradigm with long *DNA fragments* sequencing technologies, independently of the aim to resolve only one or several haplotypes. Since an *overlap* can be seen as a *succession relationship* between two oriented *fragments*, the *directed graph* structure has emerged as the more appropriate data structure for handling *overlaps*. However, this *graph* paradigm did not appear to take benefit of the *reverse* symmetry of the orientated *fragments* and their *overlaps*, which is a result of blind *DNA* double-strand sequencing. Thus, the *bi-directed graph* paradigm was introduced to be the one that reduces the *graph* size by handling the *reverse* symmetry, and since becomes the mainly used *graph* paradigm. Nevertheless, *graph* paradigms have never been contrasted before, and no implementations were described. Here we make a complete review on the existing *overlap graph* paradigms. Furthermore, we present different implementations that are theoretically compared in terms of memory, and their impact on the design and on the time of some basic *graph* algorithms. We also show that by adapting close logic implementations, a *graph* paradigm can be switched to another.

Keywords

Directed graph · Overlaps

Contents

1	Introduction	5
1.1	Reads	5
1.2	Overlaps	7
2	Storing Overlaps in a Graph Structure	9
2.1	Directed Graph: Oriented Fragments Based	11
2.2	Bi-directed Graph: Oriented Walk Based	14
2.3	Undirected Graph: Tail-Head Fragments Based	18
3	Overlap Graph Implementations	22
3.1	Directed Graph: Oriented Fragments Based	22
3.1.1	All Oriented Fragments Directed Graph (DGA)	22
3.1.2	Only Oriented Fragments' Successors Directed Graph (DGS)	25
3.1.3	Forward Fragments Directed Graph (DGF)	27
3.2	Bi-directed Graph: Oriented Walk Based	31
3.2.1	Forward Fragments Bi-directed Graph (BG)	31
3.2.2	Forward Fragments Directed Graph (DGF)	33
3.3	Undirected Graph: Tail-Head Fragments Based	33
3.3.1	All Oriented Fragments Undirected Graph (UGA)	33
3.3.2	Read-edges Jump Directed Graph (DGS)	35
4	Memory and Time Costs	35
	References	i
	Acronyms	i
	Symbols	i
	Computational	ii
	Glossary	ii

1 Introduction

What is complementary strands?

Double-stranded **Deoxyribonucleic Acid (DNA)** molecules still cannot be entirely sequenced. In fact, every *sequencing* technology (*sequencer*) generates numerous overlapping genomic *fragments*.

1.1 Reads

A **DNA fragment** obtained from a *sequencing* stage is denoted by *read*.

► Definition 1.1: Raw reads

Let \mathcal{R}_{aw} be the set of raw **reads**. $\forall r \in \mathcal{R}_{aw}$, let define the following attributes:

- $r_{rid} \in \mathbb{N}$, the **read's** integer identifier (index)
- $r_{seq} \in \Sigma^+$ the **read's** sequence, where $\Sigma = \{A, T, G, C\}$ is *nucleotide* alphabet

A **read** can be sequenced from one *strand* or from its complement.

► Axiom 1.1: Double-stranded DNA sequencing

- i. The two **DNA strands** are both sequenced.
- ii. A **strand** is read in reverse order to the order of its complementary **strand**.
- iii. Given two **reads**, it is not possible to know *a priori* it they have been sequenced from the same **strand**.

The Definition 1.2 formalises Axiom 1.1 point iii.:

► Definition 1.2: Strand identifier

Let $\text{strand_iid}: \mathcal{R}_{aw} \rightarrow \{0;1\}$ be the function which returns the **DNA strand** identifier for a **read**.

Then Axiom 1.1 point iii. can be mathematically formalised:

$$\exists (q, r) \in \mathcal{R}_{aw}^2, q \neq r \mid \text{strand_iid}(q) \neq \text{strand_iid}(r)$$

Axiom 1.1 suggests that combining two reads may result in a chimaera mix of the two strands because all the reads have not been sequenced from the same strand. Furthermore, only keeping the original sequence of the reads can result in the loss of strand parts during the *assembly* stage that aims to reconstruct the longest true parts of one strand. To solve these issues, it is sometimes necessary to consider the complementary sequence of some reads (i.e. the sequences on the complementary strand). For this, the sequence of the concerned reads are reversed (the end becomes the beginning, and vice versa) and each of its nucleotides is complemented ($A \rightleftharpoons T, G \rightleftharpoons C$). Arbitrarily, the original sequence of a read is denoted as the *forward*, while the *reverse* denotes the reverse-complement. In the following, determining what sequence is taken for a read is defined as *orienting* it. Finally, it is necessary to consider both the forward and the reverse orientation for all the reads. Figure 1 explains the meaning of forward and reverse orientations in the context of sequencing technology.

► **Definition 1.3: Reversed reads**

Let $\mathcal{R}_{ev} = \{u_r \mid u_f \in \mathcal{R}_{aw}\}$ denote the set of reversed reads. Thus $\mathcal{R} = \mathcal{R}_{aw} \cup \mathcal{R}_{ev}$. Let $u \in \mathcal{R}_{aw}$ be a read. Subscript is added to u to precise its orientation:

- u_f means that u is read in forward orientation (i.e. the original sequence of u , hence $u_f \in \mathcal{R}_{aw}$)
- u_r means that u is read in reverse orientation (i.e. the reverse-complemented sequence of u , hence $u_r \in \mathcal{R}_{ev}$)

Now the set of all oriented reads \mathcal{R} was built, the reverse operation can be defined:


► **Definition 1.4: The reverse operation for reads**

For a given read $u \in \mathcal{R}$, \bar{u} denotes its reverse, where:

- $\bar{u}_{rid} = u_{rid}$ (i.e. a read u and its reverse \bar{u} have the same identifier)
- $\bar{u}_{seq} = \overline{u_{seq}} = \overline{b_1 b_2 \cdots b_n} = \overline{b_{n-1}} \cdots \overline{b_1}$ where $n \in \mathbb{N}$ is the length of the nucleotides sequence, and $\forall i \in \llbracket 1; n \rrbracket, b_i$ is the i^{th} nucleotide base and

\bar{b}_i its complementary nucleotide base.

Note that $\overline{u_f} = u_r$ and $\overline{u_r} = u_f$.



■ **Figure 1 – Double-stranded DNA sequencing.**

u_f, v_f are two reads from the raw reads set \mathcal{R}_{aw} obtained from a double-stranded DNA sequencing stage. By default, f (forward) denotes the reading orientation of the raw reads' sequence that gives their sequence, while r (reverse) denotes the reading orientation of the raw reads' sequence that gives their reversed complemented sequence. In this illustration case, u_f was sequenced from strand $strand_0$ ($\text{strand_iid}(u_f) = 0$) while v_f was sequenced from strand $strand_1$ ($\text{strand_iid}(v_f) = 1$).

► **Axiom 1.2: Belonging to one strand**

The definition of \mathcal{R} set and Axiom 1.1 point ii. give the following statement:

$$\forall r \in \mathcal{R}, \text{strand_iid}(r) = 1 - \text{strand_iid}(\bar{r})$$

1.2 Overlaps

Reads must be assembled to reconstruct the entire genome since they are shorter than the length of the strand from which they have been sequenced (see Axiom 1.1). To assemble the reads means to find the original order of the (oriented) reads. Thus, the assembly stage is at least based on oriented reads alignments that define a succession relationship between them. One alignment type that answers this issue is overlap.

► **Definition 1.5: Overlap**

- An overlap between two nucleotides sequences (u, v) is a semi-global alignment or a close mapping between the end of sequence u_{seq} and the beginning of sequence v_{seq} .

— Let define \mathcal{O} the set of overlaps.

All four scenarios for sequence overlap are depicted in Figure 2.

► **Property 1.1: Overlap reverse symmetry**

One overlap between two sequences always implies one overlap between the reversed sequences:


$$\forall (q, r) \in \mathcal{R}^2, (q, r) \in \mathcal{O} \iff (\bar{r}, \bar{q}) \in \mathcal{O}$$

▷ Proof

From Definition 1.3, it is sufficient to take one alignment between two sequences u and v , evaluated by an alignment score, that represents an overlap (hence succession relationship), and remark that:

- i. the alignment score remains the same if the alignment is (reversely) read from v to u ,
- ii. the score remains the same if each nucleotide is transformed to its complement,
- iii. combining points i. and ii. results in an alignment between \bar{v} and \bar{u} with the same alignment score as alignment $u v$

□



■ **Figure 2 – Overlap cases between two sequences**

u and v are two sequences, represented by an arrow that shows the forward orientation. Each subfigure illustrates one overlap case: (a) u_f overlaps v_f (hence v_r overlaps u_r) (b) v_f overlaps u_f (hence u_r overlaps v_r) (c) u_f overlaps v_r (hence v_f overlaps u_r) (d) v_r overlaps u_f (hence u_r overlaps v_f).

Analogously with Definition 1.4, Definition 1.6 extends the reverse operation to overlaps:

► **Definition 1.6: The reverse operation for overlaps**

For a given overlap $(q, r) \in \mathcal{O}$, $\overline{(q, r)}$ denotes its reverse i.e. (\bar{r}, \bar{q}) .

2 Storing Overlaps in a Graph Structure

Overlaps between the reads can be represented in a *graph* structure. A graph is a mathematical object composed of *vertices* connected by *edges*. This graph structure would respect the following requirements:

1. Querying requirements

- given an oriented read, getting every overlapping oriented reads
- given two oriented reads, answering true if and only if they overlap


2. Dynamic requirements

- adding a read/overlap
- removing a read/overlap

Given all reads, the overlaps between them could be represented in a squared sparse matrix (of size \mathcal{R}^2). Sparse matrix compression as **Compressed Sparse Row (CSR)** or **Compressed Sparse Column (CSC)** are known for efficiently storing the matrix and enable fast overlap existence querying. Finally, they enable fast edges iteration, but suffer from requirements 2 and can not be immediately adapted for handling overlaps reverse symmetry.

Thus, adjacency list structure seems to be adapted to dynamically add vertices and edges.

Sections 2.1 to 2.3 below offer a complete review of graph paradigms, while Sections 3.1 to 3.3 propose graph implementations for each graph paradigm in the way of its philosophy. Figure 3 summarises the different graph paradigms and their implementations.



LEGEND

- Graph paradigms ordered chronologically
 - Graph paradigm implementations ordered by close logic
 - \mathcal{R}_{aw} Set of raw reads (fragments)
 - \mathcal{O} Set of overlaps
 - V Vertices set
 - E Edges set
- Graph paradigm**
- Theoretical graph type
 - Theoretical number of vertices and edges

Graph paradigm implementation

V	Vertices sets of all oriented fragments	Adjacency lists
V_f	and only forward fragments	i integer of range $0 \leq i < \mathcal{R}_{aw} $
N_V^-	Lists of predecessors and successors for all the vertices	ii integer of range $0 \leq ii < 2 \times \mathcal{R}_{aw} $
N_V^+		b boolean value $b \in \{0; 1\}$
N_V^O	Overlap-edges set	
N_V^R	Read-edges set	

■ **Figure 3 – Graph paradigms and their implementations respectively ordered chronologically and by logical adaptation.**

Blue boxes: they correspond to graph paradigms. They are described by the type of **graph** they represent, the number of **vertices** and **edges** if they have to be drawn. **Green boxes:** they correspond to discussed **graph** implementations. After their name, the second line gives the adjacency list(s) definition set(s), following by the description of the type it (they) contain(s), finally the last line give the length of the adjacency list(s) (i.e. the number of **vertices** for which the **neighbours** are given). *Ungraph*, *digraph*, and *bigraph* respectively stand for *undirected graph*, *directed graph* and *bi-directed graph*.

Fix Oriented FragmentS Based and Tail-head FragmentS based

2.1 Directed Graph: Oriented Fragments Based


The **directed graph** structure was the first idea to represent oriented **reads** and their **overlaps**, as **overlaps** are **succession relationships**. As far as we know, this structure was first mentioned in 1991 by Kececioglu [?]. Later, it was also described by Chin et al. [?], Kamath et al. [?], Andonov et al. [?], Shafin et al. [?] and Cheng et al. [?] in their respective **assembly** method.

► Definition 2.1: Oriented **fragment** based **directed graph**

Let $G = (V, E)$ a **directed graph** such that:

- V is the set of **vertices**, where each $v \in V$ represents an oriented **read**. For each **read**, there are two **vertices** (one for the **forward** orientation, and one for the **reverse** orientation). Thus, each $v \in V$ has the following attributes:
 - $v_{rid} \in \mathbb{N}$ the identifier of the **read** it represents
 - $v_{or} \in \{0; 1\}$ the orientation of the **read** it represents (equals to 0 if **forward**, else equals to 1 if **reverse**)
- E is the set of **edges**, where each $(u, v) \in E$ represents oriented **read** u overlapping oriented **read** v .

Figure 4 shows how each **overlap** case is represented in the **directed graph**.



■ **Figure 4 – Overlap cases in the directed graph.**

u and v are two sequences represented by two vertices each $(u_f, u_r$ and v_f, v_r). Each subfigure illustrates one overlap impact on the directed graph: **(a)** $(u_f, v_f) \in E$ (hence $(v_r, u_r) \in E$) **(b)** $(v_f, u_f) \in E$ (hence $(u_r, v_r) \in E$) **(c)** $(u_f, v_r) \in E$ (hence $(v_f, u_r) \in E$) **(d)** $(v_r, u_f) \in E$ (hence $(u_r, v_f) \in E$).

► **Property 2.1: Sizes of the oriented fragment based directed graph**

Let $G = (V, E)$ be an oriented fragment based directed graph:

- $|V| = 2 \times |\mathcal{R}_{aw}| = |\mathcal{R}|$
- $|E| = |\mathcal{O}|$

Because there are two vertices for each read, such that one of them represents the reverse of the other one, it is possible to define a reverse operation for this graph. Definition 2.2 extends Definitions 1.4 and 1.6:

► **Definition 2.2: The reverse operation for vertices and edges in the oriented fragment based directed graph**

Vertices For a given vertex $v \in V$, \bar{v} denotes its reverse, where:

- $\bar{v}_{rid} = v_{rid}$
- $\bar{v}_{or} = 1 - v_{or}$

Edges For a given edge $e = (u, v) \in E$, $\bar{e} = (\bar{v}, \bar{u})$ denotes its reverse.

Definition 2.3 specifies what a valid walk (and a valid path) is in this graph:

► **Definition 2.3: Walking in oriented fragment based directed graph**

A valid **walk** results in a valid **path** $p = v_0v_1 \cdots v_{n-1} \in V^n \mid n \in \mathbb{N}$ in the graph $G = (V, E)$ that respects the following criteria:


Contiguity Two consecutive **vertices** in the **path** must be connected by an **edge** in the **graph**:

$$\forall i \mid 0 \leq i < n - 1, (v_i, v_{i+1}) \in E$$

Exclusive orientation There is at most one orientation for each **vertex** in **path** p :

$$\forall v \in p, \bar{v} \notin p$$

Note that walking in this **graph** is quite similar that walking in a classic **directed graph**, except that it is not possible to walk through a **vertex** and its **reverse**. Figure 5 gives an example of a valid **walk** in the **directed graph**.



■ **Figure 5 – Valid walk example in the oriented fragment based directed graph.**

A valid **walk** that begins from **vertex** v_f is coloured in red. This **walk** results in a **path** $p = v_f u_f x_r$.

Finally, Property 2.2 suggests that this **directed graph** inherits a reverse symmetry property analogous to Property 1.1:

► **Property 2.2: Reverse symmetry for the vertices and the edges**

$$- \forall v \in V, \bar{v} \in V.$$

$$- \forall (u, v) \in E, \overline{(u, v)} = (\bar{v}, \bar{u}) \in E.$$

▷ Proof

By construction (see Definition 2.1), the first point is immediate. Concerning the second point, it is sufficient to note that if $(r, q) \in \mathcal{O}$ (hence $(u, v) \in E$), then $(\bar{q}, \bar{r}) \in \mathcal{O}$ (hence $(\bar{v}, \bar{u}) \in E$), where r and q are two oriented reads in \mathcal{R} , respectively represented by vertices u and v in V .

□

Figure 4 also illustrates Property 2.2.

2.2 Bi-directed Graph: Oriented Walk Based


In order to avoid creating two vertices for each read (and thus creating two edges for each overlap), the bi-directed graph structure to store overlaps was introduced by E. W. Myers in 1995 [?]. The key idea is to represent each read with only one vertex and keep the strict necessary overlap information between two reads on the edge connecting two vertices. Definition 2.4 provides a formal description. It was also described by Sommer et al. [?], Hernandez et al. [?] and Salmela et al. [?] in their respective assembly method.

► **Definition 2.4: Oriented walk based bi-directed graph**

Let $G = (V, E, or_E, rel_E)$ a bi-directed graph such that:

- V is the set of vertices, where each $v \in V$ represents a non-oriented read. For each read, there are only one vertex. Thus, each vertex $v \in V$ has an identifier of the read it represents $v_{rid} \in \mathbb{N}$.
- E is the set of edges, where each $(u, v) \in E$ represents an overlap between oriented read u and oriented read v . The overlap information are given by or_{uv} and rel_{uv} :
 - the orientation of u relatively to this of v is given by edge attribute or_E : if the orientations are the same, then $or_{uv} = 0$, else $or_{uv} = 1$
 - given that u identifier is lexicographically less than that of v , $rel_{uv} = 0$ if u in forward orientation overlaps v (in orientation given by or_{uv}), else, $rel_{uv} = 1$ if v (in orientation given by or_{uv}) overlaps u in forward orientation

While visually each edge has two extremities in the bi-directed graph, in memory the graph is undirected. Figure 6 shows how visually and how internally each overlap is stored in the bi-directed graph.



■ **Figure 6 – Overlap cases in the bi-directed graph.**

u and v are two unoriented sequences. Each subfigure illustrates one **overlap** impact on the **bi-directed graph**. For each, the first subfigure corresponds to the visualisation of a bi-directed **edge**, and the second shows the same information but with an undirected **edge** with or_{uv} and rel_{uv} attributes. **(a)** u and v have the same orientation in the **overlap** hence $or_{uv} = 0$, u in **forward** orientation overlaps v hence $rel_{uv} = 0$ **(b)** u and v have the same orientation in the **overlap** hence $or_{uv} = 0$, u in **forward** orientation is overlapped by v hence $rel_{uv} = 1$ **(c)** u and v do not have the same orientation in the **overlap** hence $or_{uv} = 1$, u in **forward** orientation overlaps v hence $rel_{uv} = 0$ **(d)** u and v do not have the same orientation in the **overlap** hence $or_{uv} = 1$, u in **forward** orientation is overlapped by v hence $rel_{uv} = 1$

► **Property 2.3: Sizes of the oriented walks based bi-directed graph**

Let $G = (V, E)$ be an oriented walks based bi-directed graph:

- $|V| = |\mathcal{R}_{aw}| = \frac{1}{2} \times |\mathcal{R}|$
- $|E| = \frac{1}{2} \times |\mathcal{O}|$

As the **vertices** represent unoriented **reads** and the **overlaps** are **succession relationships** between two oriented **reads**, it is necessary to define a variable for each **vertex** that gives its orientation:

► **Definition 2.5: Vertex orientation variable**

At each **vertex** $v \in V$ is associated a variable v_{or} that gives its orientation.

Given an **overlap** between two oriented **reads**, the variables of the two **vertices** that correspond to them (but unoriented) must respect their orientation. Definition 2.6 formalises this constraint that named co-validity constraint:

► **Definition 2.6: Co-validity for the orientation variables of the edge' extremities**

Let $(u, v) \in E$ be an edge. The orientation variables u_{or} and v_{or} are co-valid according the edge's attributes when:

- they are co-valid for or_{uv} attribute:

$$|u_{or} - v_{or}| = or_{uv}$$

- they are co-valid for rel_{uv} attribute:

$$u_{or} = \begin{cases} rel_{uv} & \text{if } u_{rid} < v_{rid} \\ |(1 - or_{uv}) - rel_{uv}| & \text{if } u_{rid} > v_{rid} \end{cases}$$

To know if the orientation variables are co-valid, the identifiers of the two consecutive vertices have to be compared. To avoid this verification, one may remark that the attribute rel_{uv} equals to $1 - rel_{vu}$, and can suggest a change in the attribute value, depending on the vertex u or v from which the edge (u, v) is considered. But this would contradict the bi-directed graph paradigm philosophy (which is a undirected graph paradigm) since having two different edge attributes rel_{uv} and rel_{vu} implies that the graph is directed.

As the graph is bi-directed, it is possible to define a reverse operation. Analogously to Definition 2.2, Definition 2.7 formalises the reverse operation in the bi-directed graph.

► **Definition 2.7: The reverse operation for vertices and edges in the oriented walk based bi-directed graph**

Vertices For a given vertex $v \in V$ and a fixed orientation variable v_{or} , \bar{v} denotes its reverse, where:

- $\bar{v}_{rid} = v_{rid}$
- $\bar{v}_{or} = 1 - v_{or}$

Edges For a given edge $e = (u, v) \in E$ and fix co-valid orientation variables u_{or} and v_{or} , $\bar{e} = (\bar{v}, \bar{u})$ denotes its reverse.

According to Definition 2.4, given $(u, v) \in E$ and one orientation for u or for v , it is necessary to check rel_{uv} value to determine the succession relationship between oriented u and oriented v . This particularity makes the bi-directed graph oriented

walk dependent. Definition 2.8 specifies what a valid *walk* is in this *graph*.

► **Definition 2.8: Walking in oriented walk based bi-directed graph**

A valid *walk* results in a *path* $p = v_0v_1 \cdots v_{n-1} \in V^n \mid n \in \mathbb{N}$ in the *graph* $G = (V, E, or_E, rel_E)$ that respects the following criteria:

Contiguity

- Two consecutive *vertices* in the *path* must be connected by an *edge* in the *graph*:


$$\forall i \mid 0 \leq i < n - 1, (v_i, v_{i+1}) \in E$$

- Given the *vertices*' orientation $v_{i_{or}}$ and $v_{i+1_{or}}$, they must be co-valid.

Exclusive orientation At most one orientation is chosen for each *vertex*:

$$\forall v_i, v_j \in p, v_i = v_j \implies i = j$$

Figure 7 gives an example of a valid *walk* in the *bi-directed graph*. Note that walking in this *graph* is not similar to walking in a classical *undirected graph* because the orientation variables must be co-valid.



■ **Figure 7 – Valid walk example in the oriented walks based bi-directed graph.**

A valid *walk* is coloured in red. As the *graph* is undirected, the resulting *path* can be read in two possible ways: from *vertex* v or from *vertex* x . Let $p_v = vux$ the one that begins from v such that $v_{or} = 0, u_{or} = 0, x_{or} = 1$. Thus, $p_x = xuv$ is the one that begins from x such that $x_{or} = 0, u_{or} = 1, v_{or} = 1$. Note that $p_x = \overline{p_v}$. In (a) edges are drawn bidirected while in (b) they are drawn undirected.

Thanks to *edges* attributes or_E and rel_E , the *bi-directed graph* inherits a reverse symmetry property analogous to Property 1.1:

► **Property 2.4: Reverse symmetry for the edges**

Given an edge $(u, v) \in E$ and its attributes or_{uv} and rel_{uv} , an overlap and its reverse are encoded in the graph.

▷ Proof

Without any loss of generality, let suppose that u identifier is lexicographically less than that of v .

- If $or_{uv} = 0$:
 - if $rel_{uv} = 0$, then: if u orientation is fixed forward, then overlap (u_f, v_f) is obtained; while if u orientation is fixed reverse, then (v_r, u_r) is obtained (because rel_{uv} determines if oriented v is after or before u in forward orientation)
 - else: if u orientation is fixed forward, then overlap (v_f, u_f) is obtained; while if u orientation is fixed reverse, then (u_r, v_r) is obtained.
- Else:
 - if $rel_{uv} = 0$, then: if u orientation is fixed forward, then overlap (u_f, v_r) is obtained; while if u orientation is fixed reverse, then (v_f, u_r) is obtained.
 - else: if u orientation is fixed forward, then overlap (v_r, u_f) is obtained; while if u orientation is fixed reverse, then (u_r, v_f) is obtained.

□

2.3 Undirected Graph: Tail-Head Fragments Based

A new undirected graph structure was presented by E. W. Myers in 2005 [?]: one read is represented by its tail and its head. Both the tail and the head are vertices, and there is one edge from the tail to the head. Passing through first the tail and then the head corresponds to choose the read in forward orientation, while passing through first the head and then the tail corresponds to choose it in reverse orientation. This new type of edges are called read-edges, at the opposite of overlap-edges that correspond to overlaps. A walk in the graph must alternate between read-edges and overlap-edges. This representation was also described in

the Mäkinen et al.'s book [?] and by Li [?] for its assembly method.


► **Definition 2.9: Tail-head Fragments Based undirected graph**

Let $G = (V, E)$ a **undirected graph** such that:

- V is the set of **vertices**, where each $v \in V$ represents one of the extremity of one **read**. For each **read**, there are two **vertices** v_t, v_h (respectively for the tail of the **read**, and for its head). Thus, each $v \in V$ has the following attributes:
 - $v_{rid} \in \mathbb{N}$ the identifier of the **read** it represents
 - $v_{ext} \in \{0; 1\}$ the extremity of the **read** it represents (equals to 0 if it is the head, else equals to 1 if it is the tail^a)
- $E = E^{\mathcal{R}} \cup E^{\mathcal{O}}$ is the set of **edges**, such that:
 - each undirected **read-edge** $(v_t, v_h) \in E^{\mathcal{R}}$ encodes the two possible **read** orientations (**forward** if from v_t to v_h , else **reverse**)
 - each undirected **overlap-edge** $(u, v) \in E^{\mathcal{O}}$ represents which extremity of **read** u is overlapping which extremity of **read** v

^aThe values for the extremities are arbitrary: while selecting 0 for the tail and 1 for the head appears more natural, switching the values will be interesting later.

Figure 8 shows for all the **overlap** cases how they are represented in the **undirected graph**.



■ **Figure 8 – Overlap cases in the undirected graph.**

u_t, u_h and v_t, v_h are respectively the tail and the head of **reads** u and v . Dashed **edges** correspond to **read-edges** while plain **edges** correspond to **overlap-edges**. Each subfigure illustrates one **overlap** impact on the **undirected graph**: **(a)** $(u_h, v_t) \in E$ **(b)** $(v_h, u_t) \in E$ **(c)** $(u_h, v_h) \in E$ **(d)** $(v_t, u_t) \in E$.

► **Property 2.5: Sizes of the tail-head fragment based undirected graph**

Let $G = (V, E)$ be an oriented walks based bi-directed graph:

- $|V| = 2 \times |\mathcal{R}_{aw}| = |\mathcal{R}|$
- $|E| = \frac{1}{2} \times |\mathcal{O}| + |\mathcal{R}_{aw}|$

As for each read there are two vertices that represent their two extremities, it is possible to define a reverse operation. Analogously to Definitions 2.2 and 2.7, Definition 2.10 formalises the reverse operation in the undirected graph.

► **Definition 2.10: The reverse operation for vertices and edges in the tail-head fragment based undirected graph**

Vertices For a given vertex $v \in V$, \bar{v} denotes its reverse, where:

- $\bar{v}_{rid} = v_{rid}$
- $\bar{v}_{or} = 1 - v_{or}$

Edges For a given edge $e = (u, v) \in E$, $\bar{e} = (v, u)$ denotes its reverse.

Because of the partition of edges set E in two subsets, walking in this graph does not correspond to a traditional undirected graph walk. Definition 2.11 specifies what a valid walk is in this graph.

► **Definition 2.11: Walking in tail-head fragments based undirected graph**

A valid walk results in a path $p = v_0 v_1 \cdots v_{2k-1} \in V^{2k} \mid k \in \mathbb{N}$ in the graph $G = (V, E^{\mathcal{R}} \cup E^{\mathcal{O}})$ that respects the following criteria:

Contiguity Read-edges and overlap-edges alternate in the path:

- odd-numbered edges in the path are read-edges:


$$\forall i \mid 0 \leq i < k, (v_{2i}, v_{2i+1}) \in E^{\mathcal{R}}$$
- even-numbered edges in the path are overlap-edges:

$$\forall i \mid 1 \leq i < k, (v_{2i-1}, v_{2i}) \in E^{\mathcal{O}}$$

Exclusive orientation At most one orientation is chosen for each vertex:

$$\forall v_i, v_j \in p, v_i = v_j \implies i = j$$

Note that walking in this **graph** is not similar that walking in a classic **undirected graph**, because a valid **walk** must alternate between **read-edges** and **overlap-edges**. Figure 5 gives an example of a valid **walk** in the **undirected graph**.



■ **Figure 9 – Valid walk example in the tail-head fragment based undirected graph.**

A valid **walk** is coloured in red. As the **graph** is undirected, the resulting **path** can be read in two possible ways: from **vertex** v_t or from **vertex** x_t . Let $p_v = v_t v_h u_t u_h x_h x_t$ the one that begins from v_t , thus $p_x = x_t x_h u_h u_t v_h v_t$ is the one that begins from x_t . Note that $p_x = \overline{p_v}$.

Because the set of **vertices** contains the two extremities of each **read**, the **undirected graph** inherits a reverse symmetry property analogous to Property 1.1:

► **Property 2.6: Reverse symmetry for the read-edges and the overlap-edges**

Given one **overlap-edge** $(u, v) \in E^{\mathcal{O}}$ and the two **read-edges** $(u_t, u_h) \in E^{\mathcal{R}}$ and $(v_t, v_h) \in E^{\mathcal{R}}$, one **overlap** and its reverse are encoded in the **graph**.

- $\forall (v_t, v_h) \in E, (v_h, v_t) \in E$, where v_t corresponds to the tail of **read** v and v_h corresponds to its head.
- $\forall (u, v) \in E, (v, u) \in E$.

▷ **Proof**

- **Read-edge** (v_t, v_h) corresponds to reading **read** v in **forward** orientation, hence (v_h, v_t) correspond to reading it in **reverse** orientation.
- Let $(u, v) \in E^{\mathcal{O}}$ be an **overlap-edge**, hence **read-edges** (\bar{u}, u) and (v, \bar{v}) are considered. Moreover, **overlap-edge** (v, u) is also in $E^{\mathcal{O}}$, hence **read-edges** (u, \bar{u}) and (\bar{v}, v) are considered, and they correspond to the

reverse of the previous read-edges.

□

Figure 8 also illustrates Property 2.6.

3 Overlap Graph Implementations

For each graph paradigm in Section 2 at least one implementation is proposed in Sections 3.1 to 3.3. A map of all implementations and the graph paradigms they follow is illustrated in Figure 3.

In the following, let consider that all the overlaps in overlaps set \mathcal{O} are kept, and reads in reads set \mathcal{R}_{aw} participate in at least one overlap. Also let suppose that $\min_{r \in \mathcal{R}_{aw}} r_{rid} = 0$ and $\max_{r \in \mathcal{R}_{aw}} r_{rid} = |\mathcal{R}_{aw}| - 1$. The previous assertions permit to easily build an index on read identifiers rid . Also, mathematical terms as $G = (V, E)$ remain the same as in Section 2.

3.1 Directed Graph: Oriented Fragments Based

Section 3.1.1 describes the first implementation idea for the oriented fragment based directed graph, while Sections 3.1.2 and 3.1.3 takes the benefits of reverse symmetry to build a more clever implementation.

3.1.1 All Oriented Fragments Directed Graph (DGA)

For each read, there are two vertices in the directed graph. Remind that each read identifier r_{rid} corresponds to a unique integer identifier (it is an index, see Definition 1.1).

The All Oriented Fragments Directed Graph (DGA) implementation is the first and the simplest idea that follows a classical directed graph implementation. Thus, for each read $r \in \mathcal{R}_{aw}$ there are two vertices $v_f, v_r \in V$ such that the index of v_f is equal to $2 \times r_{rid}$ and the index of v_r is equal to $2 \times r_{rid} + 1$. Definition 3.1 formalises indices sets.

► **Definition 3.1: Graph indices set for DGA**

Let $Vind = \llbracket 0; 2 \times |\mathcal{R}_{aw}| \rrbracket$ be the set of indices for the vertices:

$$— |Vind| = 2 \times |\mathcal{R}_{aw}|$$

- $\forall v_{ind} \in V_{ind}, v_{ind} = 2 \times v_{rid} + v_{or}$, where v_{rid} corresponds to the read's identifier and $v_{or} \in \{0; 1\}$ its orientation

Let $E_{ind} = \llbracket 0; |\mathcal{O}| \rrbracket$ be the set of indices for the edges:

- $|E_{ind}| = |\mathcal{O}|$
- $\forall e_{ind} \in E_{ind}, e_{ind}$ corresponds to the index of edge e , such that $|e_{ind} - \bar{e}_{ind}| = 1$

It is possible now to build the two adjacency lists: the first one for the *predecessors*, the second one for the *successors*. They both contain respectively the index of each predecessor, resp. of each successor vertices as the same way as a classic directed graph implementation. They also contain the index of the edge. Definition 3.2 details the way the implementation is built.

add edge index

► Definition 3.2: DGA implementation

DGA graph implementation is built by:

Predecessor list $N_V^- \forall v \in V, \forall u \in N_v^-, u_{ind}$ is the index of a predecessor of vertex v

Successor list $N_V^+ \forall v \in V, \forall w \in N_v^+, w_{ind}$ is the index of a successor of vertex v

Figure 10 illustrates the impact of overlap cases on the structure. For clarity's sake, only the indices of the predecessors (successors) are written.


Proposition 3.1 gives the amount of octet DGA implementation consumes.

► Proposition 3.1: DGA memory consumption

The memory size of the graph $Mem(DGA)$ (in octets) is equals to:

$$Mem(DGA) = 2 \times (2 \times |\mathcal{R}_{aw}| + 1) \times P \\ + 2 \times |\mathcal{O}| \times \left(\left\lceil \frac{1 + \log_2 |\mathcal{R}_{aw}|}{8} \right\rceil + \left\lceil \frac{\log_2 |\mathcal{O}|}{8} \right\rceil \right)$$

where P is the memory size of a memory address.



■ **Figure 10 – All oriented fragments directed graph implementation.** At the top left, the dot lined box corresponds to the legend for each of the four **overlap** cases. The grey mathematical formula above provides the **overlap** and its reverse symmetric **overlap**, under parenthesis, for the illustrated case. Under, there are the two adjacency lists (the first one contains the **predecessors**, the second one contains the **successors**): they both contain the indices of the **predecessors/successors**. At the top right, the grey box gives some **graph** properties.

▷ Proof

proof here □

3.1.2 Only Oriented Fragments' Successors Directed Graph (DGS)

DGA implementation suffer from redundancies in the data because it does not take benefits from the reverse symmetry. Only Oriented Fragments' Successors Directed Graph (DGS) implementation takes benefits from the symmetry hence while the structure follows the one of DGA, only the successor list is kept. Definition 3.3 details how it is built in memory.

add edge index

► Definition 3.3: DGS implementation

DGS graph implementation is built by the successor list N_v^+ such that $\forall v \in V, \forall w \in N_v^+, w_{ind}$ is the index of a successor of vertex v . Also, for each successor w of vertex v

Figure 11 illustrates the impact of each overlap type on DGS implementation. For clarity's sake, only the indices of the successors are written, but not the edge indices.

Proposition 3.2 gives the amount of octet DGS implementation consumes.

► Proposition 3.2: DGS memory consumption

The memory size of the graph $Mem(DGS)$ (in octets) is equals to:

$$Mem(DGS) = (2 \times |\mathcal{R}_{aw}| + 1) \times P + |\mathcal{O}| \times \left(\left\lceil \frac{1 + \log_2 |\mathcal{R}_{aw}|}{8} \right\rceil + \left\lceil \frac{\log_2 |\mathcal{O}|}{8} \right\rceil \right)$$


where P is the memory size of a memory address.

▷ Proof

For each vertex there is a pointer to its successor list, hence $2 \times |\mathcal{R}_{aw}|$ pointers, and there is one pointer to the vertices' successor list. Then, for each successor, its index is provided ($\lceil \log_2 2 \times |\mathcal{R}_{aw}| \rceil$ bits), and the edge index is provided too ($\lceil \log_2 |\mathcal{O}| \rceil$ bits). These numbers are divided by eight and rounded up to the nearest integer to get the number of octets. Then the sum is multiplied by the number of overlaps ($|\mathcal{O}|$).

□

verify if same with commented



■ **Figure 11 – Only oriented fragments successors directed graph implementation.**

At the top left, the dot lined square corresponds to the legend for each of the four **overlap** cases. The grey mathematical formula above provides the **overlap** and its reverse symmetric **overlap**, under parenthesis, for the illustrated case. Under, there is the **successor** list: it contains the indices of the **successors**. At the top right, the grey square gives some **graph** properties.

Proposition 3.3 answer the issue of getting the **predecessors**.

► **Proposition 3.3: DGS reverse symmetry to retrieve predecessors**

For each **vertex** $v \in V$:

- i. its **predecessors** are the **reverse** of its **reverse'** **successors**

ii. the **edge** index of $(u, v) \in E$ is the **reverse** of this of $(\bar{v}, \bar{u}) \in E$

▷ **Proof**

Let $v \in V$ be a **vertex**. Let $u \in V$ such that $(u, v) \in E$. Thus:

i. $(\bar{v}, \bar{u}) \in E$, hence \bar{u} is the **successor** of \bar{v} that is the **reverse** of v .

Finally, $\bar{\bar{u}} = u$, that is the **predecessor** of v .

ii. If \bar{e}_{ind} is the **edge** index of **edge** (\bar{v}, \bar{u}) , then $e_{ind} = \bar{e}_{ind} + c$ (where $c = 1$ if \bar{e}_{ind} is even, else $c = -1$) corresponds to the **edge** index of the **reverse** of (\bar{v}, \bar{u}) hence the **edge** index of (u, v) .

□

3.1.3 Forward Fragments Directed Graph (DGF)

As for **DGS** implementation, the last implementation of the **directed graph** structure, **Forward Fragments Directed Graph (DGF)**, takes benefits from the **reverse** symmetry. **DGF** focuses only on the **neighbours** of the **vertices** that represent the **reads** in **forward** orientation (hence the **reads** in raw **reads** set \mathcal{R}_{aw}). Therefore, the **vertices** indices set is not build as previously. Hence for each **read** $r \in \mathcal{R}_{aw}$, let $v_{ind} = r_{rid}$ be the index of the **vertex** that represents it. Because an **overlap** involves two oriented **reads**, the **neighbours'** orientation must be included to the adjacency lists. Hence for each **neighbour** $v \in V$ in the **predecessors/successor** lists of a **forward vertex**, let $v_{indor} = (v_{ind}, v_{or})$ be its oriented **neighbour**. Definition 3.4 describes the different sets, and Definition 3.5 details the **DGF** implementation. For clarity's sake, only the indices of the **predecessors/successors** are written, but not the **edge** indices.

► **Definition 3.4: Graph indices set for DGA**

Let $V_{ind} = \llbracket 0; |\mathcal{R}_{aw}| \rrbracket$ be the set of indices for the **vertices**:

— $|V_{ind}| = |\mathcal{R}_{aw}|$

— $\forall v_{ind} \in V_{ind}, v_{ind} = v_{rid}$, where v_{rid} corresponds to the **read's** identifier

Let $V_{indor} = \llbracket 0; |\mathcal{R}_{aw}| \rrbracket \times \{0; 1\}$ be the set of indices enriched by a boolean value for the oriented **vertices**:

— $|V_{indor}| = 2 \times |\mathcal{R}_{aw}|$

- $\forall v_{indor} \in V_{indor}, v_{indor} = (v_{rid}, v_{or})$, where v_{rid} corresponds to the read's identifier and v_{or} to its orientation

Let $E_{ind} = \llbracket 0; |\mathcal{O}| \rrbracket$ be the set of indices for the edges:

- $|E_{ind}| = |\mathcal{O}|$
- $\forall e_{ind} \in E_{ind}, e_{ind}$ corresponds to the index of edge e , such that $|e_{ind} - \bar{e}_{ind}| = 1$

add edge index

► Definition 3.5: DGF implementation

DGF graph implementation is built by:

Predecessor list for the forward $N_{V_f}^- \forall v \in V_f, \forall u \in N_v^-, u_{ind}$ is the index of a predecessor of vertex v , and u_{or} gives its orientation

Successor list for the forward $N_{V_f}^+ \forall v \in V_f, \forall w \in N_v^+, w_{ind}$ is the index of a successor of vertex v , and w_{or} gives its orientation

► Proposition 3.4: DGF memory consumption


The memory size of the graph $Mem(DGF)$ (in octets) is equals to:

$$Mem(DGF) = 2 \times (|\mathcal{R}_{aw}| + 1) \times P \\ + |\mathcal{O}| \times \left(\left\lceil \frac{1 + \log_2 |\mathcal{R}_{aw}|}{8} \right\rceil + \left\lceil \frac{\log_2 |\mathcal{O}|}{8} \right\rceil \right)$$

where P is the memory size of a memory address.

▷ Proof

For each (*forward*) vertex there is a pointer to its predecessor and successor lists, hence $2 \times |\mathcal{R}_{aw}|$ pointers, and there is one pointer to the vertices' predecessor and successor lists (hence +2). Then, for each predecessor/successor, its index and a boolean orientation value are provided ($\lceil \log_2 2 \times |\mathcal{R}_{aw}| \rceil$ bits), and the edge index is provided too ($\lceil \log_2 |\mathcal{O}| \rceil$ bits). These numbers are divided by eight and rounded up to the nearest integer to get the number of



■ **Figure 12 – Forward fragments directed graph implementation.**

At the top left, the dot lined square corresponds to the legend for each of the four **overlap** cases. The grey mathematical formula above provides the **overlap** and its reverse symmetric **overlap**, under parenthesis, for the illustrated case. Under, there are the two adjacency lists for the **forward** (the first one contains the **predecessors**, the second one contains the **successors**): they both contain the couples index-orientation of the **predecessors/successors**. At the top right, the grey square gives some **graph** properties.

octets. Then the sum is multiplied by the number of overlaps ($|\mathcal{O}|$).

□

verify if same with commented

Note that in contrast to Proposition 3.2, the memory consumption of adjacency lists pointers is equals to $2 \times (|\mathcal{R}_{aw}| + 1)$ (versus $(2 \times |\mathcal{R}_{aw}| + 1)$). In fact, the extra P is due to an extra adjacency list.

Proposition 3.5 answer the issue of getting the predecessors/successors of the reverse.

► **Proposition 3.5: DGF reverse symmetry to retrieve predecessors**

For each vertex $v \in V_r$:

- i. its predecessors are the reverse of its reverse' successors
- ii. its successors are the reverse of its reverse' predecessors
- iii. the edge index of $(u, v) \in E$ is the reverse of this of $(\bar{v}, \bar{u}) \in E$

▷ Proof

Let $v \in V_r$ be a vertex that represents a reverse read.

— Let $u \in V$ such that $(u, v) \in E$. Thus:

i. $(\bar{v}, \bar{u}) \in E$, hence \bar{u} is the successor of \bar{v} that is the reverse of v .

Finally, $\bar{\bar{u}} = u$, that is the predecessor of v .

ii. If \bar{e}_{ind} is the edge index of edge (\bar{v}, \bar{u}) , then $e_{ind} = \bar{e}_{ind} + c$ (where $c = 1$ if \bar{e}_{ind} is even, else $c = -1$) corresponds to the edge index of the reverse of (\bar{v}, \bar{u}) hence the edge index of (u, v) .

— Let $w \in V$ such that $(v, w) \in E$. Thus:

i. $(\bar{w}, \bar{v}) \in E$, hence \bar{w} is the predecessor of \bar{v} that is the reverse of v . Finally, $\bar{\bar{w}} = w$, that is the successor of v .

ii. If \bar{e}_{ind} is the edge index of edge (\bar{w}, \bar{v}) , then $e_{ind} = \bar{e}_{ind} + c$ (where $c = 1$ if \bar{e}_{ind} is even, else $c = -1$) corresponds to the edge index of the reverse of (\bar{w}, \bar{v}) hence the edge index of (v, w) .

□

3.2 Bi-directed Graph: Oriented Walk Based

3.2.1 Forward Fragments Bi-directed Graph (BG)

In the **bi-directed graph**, there is one **vertex** for each raw **read** in \mathcal{R}_{aw} . Hence for each **vertex** v is associated an index $v_{ind} = v_{rid}$. An **overlap** and its **reverse** are represented by only one **edge** that carries strictly necessary **overlap** attributes, as described in Definition 2.4. Remind that the **bi-directed graph** is equivalent to a **undirected graph**: that's implemented by **Unoriented Fragments Bi-directed Graph (BG)** implementation. Definition 3.4 describes the different sets, and Definition 3.5 details the **DGF** implementation. For clarity's sake, only the indices of the **predecessors/successors** are written, but not the **edge** indices.

► **Definition 3.6: Graph indices set for BG**

Let $V_{ind} = \llbracket 0; |\mathcal{R}_{aw}| \rrbracket$ be the set of indices for the **vertices**:

- $|V_{ind}| = |\mathcal{R}_{aw}|$
- $\forall v_{ind} \in V_{ind}, v_{ind} = v_{rid}$, where v_{rid} corresponds to the **read's** identifier

Let $E_{ind} = \llbracket 0; \frac{1}{2} \times |\mathcal{O}| \rrbracket$ be the set of indices for the **edges**:

- $|E_{ind}| = \frac{1}{2} \times |\mathcal{O}|$
- $\forall e_{ind} \in E_{ind}, e_{ind}$ corresponds to the index of **edge** e

put paragraph in definition


Concerning the edge indices e_{ind} , it is possible to use their euclidean quotient by two e'_{ind} in memory and retrieving them thanks to the orientation of the fewer vertex index (let say u). In fact, if the considered overlap uses u_f , then $e_{ind} = 2 \times e'_{ind}$, else $e_{ind} = 2 \times e'_{ind} + 1$

► **Definition 3.7: BG implementation**

BG graph implementation is built by:

Neighbours list for the forward $N_V \forall v \in V, \forall w \in N_v, w_{ind}$ is the index of a **neighbour** of **vertex** v

Edges attributes for each **neighbour** w of a **vertex** v two boolean values are provided: or_{vw} and rel_{vw} (see Definition 2.4)



■ **Figure 13** – caption title All four **overlap** cases structured in the **bi-directed graph**.

At the top, the dot lined square corresponds to the legend for the four **overlap** cases. The mathematical formula above the line is the **overlap** such that u is in **forward** orientation, and the reverse symmetric **overlap** is under parenthesis. Under the line, there is the one list that contains, in order, the index of the **neighbour**, the value of or_{uv} and the value of rel_{uv} .

► **Proposition 3.6: BG memory consumption**

The memory size of the graph $Mem(BG)$ (in octets) equals:

$$\begin{aligned}
 Mem(BG) = & (|\mathcal{R}_{aw}| + 2) \times P \\
 & + |\mathcal{O}| \times \left(\left\lceil \frac{\log_2 |\mathcal{R}_{aw}|}{8} \right\rceil + \left\lceil \frac{\log_2 |\mathcal{O}| - 1}{8} \right\rceil \right) \\
 & + \left\lceil \frac{|\mathcal{O}|}{8} \right\rceil
 \end{aligned}$$

where P is the memory size of a memory address.

▷ Proof

For each (unoriented) *vertex* there is a pointer to its *neighbour list*, hence $|\mathcal{R}_{aw}|$ pointers, and there is one pointer to the *vertices' neighbour list* and one to the *edges attribute list* (hence +2). Then, for each *neighbour*, its index is provided ($\lceil \log_2 |\mathcal{R}_{aw}| \rceil$ bits), and the *edge index* is provided too ($\lceil \log_2 (\frac{1}{2} \times |\mathcal{O}|) \rceil$ bits). These numbers are divided by eight and rounded up to the nearest integer to get the number of octets. Then the sum is multiplied by the number of *overlaps* ($|\mathcal{O}|$). Finally, for each *edge index* ($\frac{1}{2} \times |\mathcal{O}|$), there are two boolean *edge attributes*. $\frac{1}{2} \times |\mathcal{O}| \times 2$ is divided by eight and rounded up to get the number of octets. □

verify if same as comments

The four combinations of edges' attributes *or* and *rel* let representing all the overlap cases and their reverse without any redundancy. To verify the reverse symmetry, it is sufficient (and easier) to choose an orientation of u and calculate the overlap case with the edges' attributes.

3.2.2 Forward Fragments Directed Graph (DGF)

description

ref figure from digraph implementation revsymg

memory

3.3 Undirected Graph: Tail-Head Fragments Based


3.3.1 All Oriented Fragments Undirected Graph (UGA)

fix for ungraph

For each *read*, there are two *vertices* in the *directed graph*. Remind that each *read* identifier r_{rid} correspond to a unique integer identifier (it is an index,

see Definition 1.1). Thus, for each read $r \in \mathcal{R}_{aw}$ there are two vertices $v_f, v_r \in V$ such that the index of v_f is equal to $2 \times r_{rid}$ and the index of v_r is equal to $2 \times r_{rid} + 1$.

It is possible now to build the adjacency lists (one list for the predecessors, and another one for the successors).



■ **Figure 14 – caption title** All four overlap cases structured in the directed graph.

At the top left, the dot lined square corresponds to the legend for the four overlap cases. The grey mathematical formula above is the overlap such that u is in forward orientation, and the reverse symmetric overlap is under parenthesis. Under, there are the two adjacency lists (the first one contains the neighbours for overlap-edges, the second one contains the neighbours for read-edge): they both contain the indices of the neighbours. Top right grey square gives some graph properties.

memory

3.3.2 Read-edges Jump Directed Graph (DGS)

description

Cref figure only oriented frag succs digraph

memory

remarque que l'on peut arriver visuellement au digraph

4 Memory and Time Costs

stockage

iter preds/succs

add vertex

delete vertex

add edge

delete edge

All algorithms

For a vertex/edge index that represents the forward/reverse read/edge according to its parity, the reverse algorithm cost two elementary operations. For clarity's sake, $\text{rev}(ind) = \overline{ind}$.

complete the cases

— DGS best case:

Algorithm 1 Reverse operation on index

Require: Vertex/edge index ind .

Ensure: Returns index of the reverse vertex/edge.

```

1: function REV( $ind$ )
2:   if  $ind \mid 2$  then
3:     return  $ind + 1$ 
4:   return  $ind - 1$ 

```

Require: Graph $G = (V, E)$, vertex $v \in V$, orientation of v $v_{or} \in \{0; 1\}$, empty list $preds$.

Ensure: The returned list contains the predecessors of v in graph G and the corresponding edge index.

```

1:  $preds \leftarrow \text{empty\_list}()$ 
2: function DGS_PREDS( $G, v, preds$ )
3:   for  $(u, e_{ind}) \in N_v^+$  do
4:      $preds.append(\bar{u}, \bar{e}_{ind})$ 
5:   return  $preds$ 

```

```

1: function DGF_PREDS( $G, v, v_{or}, preds$ )
2:   if  $v_{or} = 0$  then  $\triangleright v$  forward
3:     for  $(u, e_{ind}) \in N_v^-$  do
4:        $preds.append(u, e_{ind})$ 
5:   else
6:     for  $(u, u_{or}, e_{ind}) \in N_v^+$  do
7:        $preds.append(u, 1 - u_{or}, \bar{e}_{ind})$ 
8:   return  $preds$ 

```

— DGS worst case:

$$\begin{aligned}
& 9 \times o_v \\
& + 3 \times \left(\sum_{u \in N_v^-} o_u^+ + \sum_{w \in N_v^+} o_w^- + \sum_{x \in N_z^-} o_x^+ + \sum_{y \in N_z^+} o_y^- \right) \\
& + 5 \times (o_z + 1)
\end{aligned}$$

Algorithm 2 Iterate over the predecessors

```

1: function BG_PREDS( $G, v, v_{or}, preds$ )
2:    $orientations \leftarrow (0, 1)$   $\triangleright$  forward/reverse orientations
3:   for  $(u, e'_{ind}) \in N_v$  do
4:     if  $v < u$  then
5:       if  $v_{or} = 0$  then
6:         if  $rel_{uv} = 1$  then  $\triangleright u_f \rightarrow v_f$  or  $u_r \rightarrow v_f$ 
7:            $preds.append(u, orientations[or_{uv}], 2 \times e'_{ind})$ 
8:         else if  $rel_{uv} = 0$  then  $\triangleright u_f \rightarrow v_r$  or  $u_r \rightarrow v_r$ 
9:            $preds.append(u, orientations[1 - or_{uv}], 2 \times e'_{ind} + 1)$ 
10:        else if  $v_{or} = 1$  then
11:          if  $or_{uv} = 0$  then
12:            if  $rel_{uv} = 0$  then  $\triangleright u_f \rightarrow v_f$ 
13:               $preds.append(u, 0, 2 \times e'_{ind})$ 
14:            else if  $rel_{uv} = 1$  then  $\triangleright u_r \rightarrow v_f$ 
15:               $preds.append(u, 1, 2 \times e'_{ind} + 1)$ 
16:          else if  $or_{uv} = 1$  then
17:            if  $rel_{uv} = 1$  then  $\triangleright u_r \rightarrow v_r$ 
18:               $preds.append(u, 1, 2 \times e'_{ind} + 1)$ 
19:            else if  $rel_{uv} = 0$  then  $\triangleright u_f \rightarrow v_r$ 
20:               $preds.append(u, 0, 2 \times e'_{ind})$ 
21:   return  $preds$ 

```

Require: Graph $G = (V, E)$, vertex $v \in V$, orientation of v $v_{or} \in \{0; 1\}$, empty list $succs$.

Ensure: The returned list contains the successors of v in graph G .

```

1:  $succs \leftarrow empty\_list()$ 
2: function DGS_SUCCS( $G, v, succs$ )
3:   for  $(w, e_{ind}) \in N_v^+$  do
4:      $succs.append(w, e_{ind})$ 
5:   return  $succs$ 

```

— DGS average case

$$\begin{aligned}
& 10 \times o_v + \frac{10 \times \mathcal{R}_{aw} - 5}{2 \times \mathcal{R}_{aw}} \times o_z \\
& + 3 \times \left(\sum_{u \in N_v^-} \left\lceil \frac{o_u^+}{2} \right\rceil + \sum_{w \in N_v^+} \left\lceil \frac{o_w^-}{2} \right\rceil \right) \\
\hline
\text{V. Epain} \quad & + \frac{6 \times \mathcal{R}_{aw} - 3}{2 \times \mathcal{R}_{aw}} \times \left(\sum_{x \in N_z^-} \left\lceil \frac{o_x^+}{2} \right\rceil + \sum_{y \in N_z^+} \left\lceil \frac{o_y^-}{2} \right\rceil \right) \quad 37 \\
& - \left(\sum_{u \in N_v^-} \frac{1}{o_u^+} + \sum_{w \in N_v^+} \frac{1}{o_w^-} \right) \\
& + 5
\end{aligned}$$

```

1: function DGF_SUCCS( $G, v, v_{or}, succs$ )
2:   if  $v_{or} = 0$  then  $\triangleright v$  forward
3:     for  $(w, e_{ind}) \in N_v^+$  do
4:        $succs.append(w, e_{ind})$ 
5:   else
6:     for  $(w, w_{or}, e_{ind}) \in N_v^-$  do
7:        $succs.append(w, 1 - w_{or}, \overline{e_{ind}})$ 
8:   return  $succs$ 

```

Algorithm 3 Iterate over the successors

```

1: function BG_SUCCS( $G, v, v_{or}, succs$ )
2:    $orientations \leftarrow (0, 1)$   $\triangleright$  forward/reverse orientations
3:   for  $(w, e'_{ind}) \in N_v$  do
4:     if  $v < w$  then
5:       if  $v_{or} = 0$  then
6:         if  $rel_{vw} = 0$  then  $\triangleright v_f \rightarrow w_f$  or  $v_f \rightarrow w_r$ 
7:            $succs.append(w, orientations[or_{vw}], 2 \times e'_{ind})$ 
8:         else if  $rel_{uw} = 1$  then  $\triangleright v_r \rightarrow w_f$  or  $v_r \rightarrow w_r$ 
9:            $succs.append(u, orientations[1 - or_{uw}], 2 \times e'_{ind} + 1)$ 
10:      else if  $v_{or} = 0$  then
11:        if  $or_{uw} = 0$  then
12:          if  $rel_{uw} = 1$  then  $\triangleright v_f \rightarrow w_f$ 
13:             $succs.append(w, 0, 2 \times e'_{ind})$ 
14:          else if  $rel_{uw} = 0$  then  $\triangleright v_f \rightarrow w_r$ 
15:             $succs.append(w, 1, 2 \times e'_{ind} + 1)$ 
16:        else if  $or_{uw} = 0$  then
17:          if  $rel_{uw} = 0$  then  $\triangleright v_r \rightarrow w_r$ 
18:             $succs.append(w, 1, 2 \times e'_{ind} + 1)$ 
19:          else if  $rel_{uw} = 1$  then  $\triangleright v_r \rightarrow w_f$ 
20:             $succs.append(w, 0, 2 \times e'_{ind})$ 
21:   return  $succs$ 

```

— DGF best case:

Require: Graph $G = (V, E)$.

Ensure: Returns the new vertex' index (in forward orientation if there is the choice).

```

1: function DGS_ADD_VERTEX( $G$ )
2:    $N_V^+$ .append(empty_list())
3:    $N_V^+$ .append(empty_list())
4:   return  $|N_V^+| - 2$ 

```

```

1: function DGF_ADD_VERTEX( $G$ )
2:    $N_V^-$ .append(empty_list())
3:    $N_V^+$ .append(empty_list())
4:   return  $|N_V^+| - 1$ 

```

Algorithm 4 Add a new vertex in the graph

```

1: function BG_ADD_VERTEX( $G$ )
2:    $N_V$ .append(empty_list())
3:   return  $|N_V| - 1$ 

```

Require: Graph $G = (V, E)$, $(u, v) \in V^2$ (with their orientation $(u_{or}, v_{or}) \in \{0; 1\}^2$ if necessary). Note that the vertices are already in the graph.

Ensure: Returns the new edge's index (in forward orientation if there is the choice).

```

1: function DGS_ADD_EDGE( $G, u, v$ )
2:    $\triangleright$  ind_edges is the number of edges. It is always even.  $\triangleleft$ 
3:    $N_u^+$ .append( $v, ind\_edges$ )
4:    $N_v^+$ .append( $\bar{u}, ind\_edges + 1$ )
5:    $ind\_edges \leftarrow ind\_edges + 2$ 
6:    $card\_edges \leftarrow card\_edges + 2$ 
7:   return  $ind\_edges - 2$ 

```

— DGF worst case:

$$\begin{aligned}
& 9 \times o_v + 4 \times o_z \\
& + 3 \times \left(\sum_{u \in N_v^-} o_u^- + \sum_{w \in N_v^+} o_w^+ + \sum_{x \in N_z^-} o_x^- + \sum_{y \in N_z^+} o_y^+ \right) \\
& + 4
\end{aligned}$$

```

1: function DGF_ADD_EDGE( $G, u, u_{or}, v, v_{or}$ )
2:    $\triangleright$  ind_edges is the number of edges. It is always even.  $\triangleleft$ 
3:   if  $u_{or} = 0$  then  $\triangleright u_f \rightarrow v_f$  or  $u_f \rightarrow v_r$ 
4:      $N_u^+$ .append( $v, v_{or}, ind\_edges$ )
5:   else  $\triangleright u_f \leftarrow v_f$  or  $u_f \leftarrow v_r$ 
6:      $N_u^-$ .append( $v, 1 - v_{or}, ind\_edges + 1$ )
7:   if  $v_{or} = 0$  then  $\triangleright u_f \rightarrow v_f$  or  $u_r \rightarrow v_f$ 
8:      $N_v^-$ .append( $u, u_{or}, ind\_edges$ )
9:   else  $\triangleright u_f \leftarrow v_f$  or  $u_r \leftarrow v_f$ 
10:     $N_v^+$ .append( $u, 1 - u_{or}, ind\_edges + 1$ )
11:     $ind\_edges \leftarrow ind\_edges + 2$ 
12:     $card\_edges \leftarrow card\_edges + 2$ 
13:  return  $ind\_edges - 2$ 

```

Algorithm 5 Add a new edge (and its reverse) in the graph

```

1: function BG_ADD_EDGE( $G, u, u_{or}, v, v_{or}$ )
2:    $\triangleright$  ind_edges is the number of edges.  $E_{attr}$  is a list of edges attributes.  $\triangleleft$ 
3:    $or \leftarrow |u_{or} - v_{or}|$ 
4:   if  $u < v$  then
5:      $rel \leftarrow u_{or}$ 
6:   else
7:      $rel \leftarrow 1 - v_{or}$ 
8:    $N_u$ .append( $v, ind\_edges$ )
9:    $N_v$ .append( $u, ind\_edges$ )
10:   $E_{attr}$ .append( $or, rel$ )
11:   $ind\_edges \leftarrow ind\_edges + 1$ 
12:   $card\_edges \leftarrow card\_edges + 1$ 
13:  return  $2 \times (ind\_edges - 1)$ 

```

— DGF average case

$$\begin{aligned}
& \frac{15}{2} \times o_v + \frac{6 \times \mathcal{R}_{aw} - 3}{2 \times \mathcal{R}_{aw}} \times o_z \\
& + \frac{3}{2} \times \sum_{u \in N_v^- \cup N_v^+} \left(\left\lceil \frac{o_u^-}{2} \right\rceil + \left\lceil \frac{o_u^+}{2} \right\rceil \right) \\
& + \frac{6 \times \mathcal{R}_{aw} - 3}{4 \times \mathcal{R}_{aw}} \times \sum_{x \in N_z^- \cup N_z^+} \left(\left\lceil \frac{o_x^-}{2} \right\rceil + \left\lceil \frac{o_x^+}{2} \right\rceil \right) \\
& - \frac{1}{2} \times \left(\sum_{u \in N_v^-} \frac{1}{o_u^+} + \sum_{w \in N_v^+} \frac{1}{o_w^-} \right)
\end{aligned}$$

- BGU best case:
- BGU worst case:
- BGU average case:

$$\begin{aligned}
& 5 \times o_v + \frac{3 \times \mathcal{R}_{aw} - 3}{\mathcal{R}_{aw}} \times o_z \\
& + 3 \times \sum_{w \in N_v} \left\lceil \frac{o_w}{2} \right\rceil + \frac{3 \times \mathcal{R}_{aw} + 3}{2 \times \mathcal{R}_{aw}} \times \sum_{y \in N_z} \left\lceil \frac{o_y}{2} \right\rceil \\
& - \sum_{w \in N_v} \frac{1}{o_w} \\
& + \frac{4 \times \mathcal{R}_{aw} - 1}{\mathcal{R}_{aw}}
\end{aligned}$$

Require: Graph $G = (V, E)$, vertex $v \in V$ (in forward orientation).

Ensure: Delete the vertex and its reverse such that $V' = V \setminus \{v, \bar{v}\}$, and $\forall v \in V', 0 \leq v_{ind} \leq |V'| - 2$.

```

1: function DGS_DELETE_VERTEX( $G, v$ )
2:   ▷ Delete it from its predecessors ◁
3:    $v\_rev \leftarrow v + 1$ 
4:   for  $(u, e_{ind}) \in N_{v\_rev}^+$  do
5:      $u\_rev \leftarrow \bar{u}$ 
6:      $adj\_ind \leftarrow \text{get\_index}(N_{u\_rev}^+, \overline{e_{ind}}, 1)$ 
7:     if  $adj\_ind = |N_{u\_rev}^+| - 1$  then
8:       ▷ Just delete the last element ◁
9:        $N_{u\_rev}^+.\text{pop}()$ 
10:    else
11:      ▷ Replace the edge by the last in the neighbour list ◁
12:       $N_{u\_rev}^+[adj\_ind] \leftarrow N_{u\_rev}^+.\text{pop}()$ 
13:       $card\_edges \leftarrow card\_edges - 2$ 
14:    delete( $N_{v\_rev}^+$ )
15:    ▷ Delete it from its successors ◁
16:    for  $(w, e_{ind}) \in N_v^+$  do
17:       $w\_rev \leftarrow \bar{w}$ 
18:       $adj\_ind \leftarrow \text{get\_index}(N_{w\_rev}^+, \overline{e_{ind}}, 1)$ 
19:      if  $adj\_ind = |N_{w\_rev}^+| - 1$  then
20:        ▷ Just delete the last element ◁
21:         $N_{w\_rev}^+.\text{pop}()$ 
22:      else
23:        ▷ Replace the edge by the last in the neighbour list ◁
24:         $N_{w\_rev}^+[adj\_ind] \leftarrow N_{w\_rev}^+.\text{pop}()$ 
25:         $card\_edges \leftarrow card\_edges - 2$ 
26:      delete( $N_v^+$ )
27:      ▷ Delete the whole vertex ◁
28:      if  $v = |N_V^+| - 2$  then
29:        ▷ It is the last, just pop it and its reverse ◁
30:         $N_V^+.\text{pop}()$ 
31:         $N_V^+.\text{pop}()$ 
32:      else
33:        ▷ Replace it and its reverse by the last and its reverse ◁
34:         $N_{v\_rev}^+ \leftarrow N_V^+.\text{pop}()$ 
35:         $N_v^+ \leftarrow N_V^+.\text{pop}()$ 
36:        ▷ Update the vertex index ◁
37:        for  $(w, e_{ind}) \in N_v^+$  do
38:           $w\_rev \leftarrow \bar{w}$ 
39:           $e_{ind\_rev} \leftarrow \overline{e_{ind}}$ 
40:           $adj\_ind \leftarrow \text{get\_index}(N_{w\_rev}^+, e_{ind\_rev}, 1)$ 
41:           $N_{w\_rev}^+[adj\_ind] \leftarrow (v\_rev, e_{ind\_rev})$ 
42:          for  $(w, e_{ind}) \in N_{v\_rev}^+$  do
43:             $w\_rev \leftarrow \bar{w}$ 
44:             $e_{ind\_rev} \leftarrow \overline{e_{ind}}$ 
45:             $adj\_ind \leftarrow \text{get\_index}(N_{w\_rev}^+, e_{ind\_rev}, 1)$ 
46:             $N_{w\_rev}^+[adj\_ind] \leftarrow (v, e_{ind\_rev})$ 

```

```

1: function DGF_DELETE_VERTEX( $G, v$ )
2:   ▷ Delete it from its predecessors ◁
3:   for  $(u, u_{or}, e_{ind}) \in N_v^-$  do
4:     if  $u_{or} = 0$  then
5:        $adj\_ind \leftarrow \text{get\_index}(N_u^+, e_{ind}, 1)$ 
6:       if  $adj\_ind = |N_u^+| - 1$  then
7:         ▷ Just delete the last element ◁
8:          $N_u^+.\text{pop}()$ 
9:       else
10:        ▷ Replace the edge by the last in the neighbour list ◁
11:         $N_u^+[adj\_ind] \leftarrow N_u^+.\text{pop}()$ 
12:      else
13:         $adj\_ind \leftarrow \text{get\_index}(N_u^-, \overline{e_{ind}}, 1)$ 
14:        if  $adj\_ind = |N_u^-| - 1$  then
15:          ▷ Just delete the last element ◁
16:           $N_u^-.\text{pop}()$ 
17:        else
18:          ▷ Replace the edge by the last in the neighbour list ◁
19:           $N_u^-[adj\_ind] \leftarrow N_u^-.\text{pop}()$ 
20:         $card\_edges \leftarrow card\_edges - 2$ 
21:      delete( $N_v^-$ )
22:      ▷ Delete it from its successors ◁
23:      for  $(w, w_{or}, e_{ind}) \in N_v^+$  do
24:        if  $w_{or} = 0$  then
25:           $adj\_ind \leftarrow \text{get\_index}(N_w^-, e_{ind}, 1)$ 
26:          if  $adj\_ind = |N_w^-| - 1$  then
27:            ▷ Just delete the last element ◁
28:             $N_w^-.\text{pop}()$ 
29:          else
30:            ▷ Replace the edge by the last in the neighbour list ◁
31:             $N_w^-[adj\_ind] \leftarrow N_w^-.\text{pop}()$ 
32:          else
33:             $adj\_ind \leftarrow \text{get\_index}(N_w^+, \overline{e_{ind}}, 1)$ 
34:            if  $adj\_ind = |N_w^+| - 1$  then
35:              ▷ Just delete the last element ◁
36:               $N_w^+.\text{pop}()$ 
37:            else
38:              ▷ Replace the edge by the last in the neighbour list ◁
39:               $N_w^+[adj\_ind] \leftarrow N_w^+.\text{pop}()$ 
40:             $card\_edges \leftarrow card\_edges - 2$ 
41:          delete( $N_v^+$ )

```

```

1: function DGF_DELETE_VERTEX_SUITE( $G, v$ )
2:    $\triangleright$  Delete the whole vertex ◁
3:   if  $v = |N_V^+| - 1$  then
4:      $\triangleright$  It is the last, just pop it and its reverse ◁
5:      $N_V^-.pop()$ 
6:      $N_V^+.pop()$ 
7:   else
8:      $\triangleright$  Replace it and its reverse by the last and its reverse ◁
9:      $N_v^- \leftarrow N_V^-.pop()$ 
10:     $N_v^+ \leftarrow N_V^+.pop()$ 
11:     $\triangleright$  Update the vertex index ◁
12:    for  $(u, u_{or}, e_{ind}) \in N_v^-$  do
13:      if  $u_{or} = 0$  then
14:         $adj\_ind \leftarrow get\_index(N_u^+, e_{ind}, 1)$ 
15:         $N_u^+[adj\_ind] \leftarrow (v, 0, e_{ind})$ 
16:      else
17:         $u\_rev \leftarrow \bar{u}$ 
18:         $e_{ind\_rev} \leftarrow \overline{e_{ind}}$ 
19:         $adj\_ind \leftarrow get\_index(N_{u\_rev}^-, e_{ind\_rev}, 1)$ 
20:         $N_{u\_rev}^-[adj\_ind] \leftarrow (v, 1, e_{ind\_rev})$ 
21:    for  $(w, w_{or}, e_{ind}) \in N_v^+$  do
22:      if  $w_{or} = 0$  then
23:         $adj\_ind \leftarrow get\_index(N_w^-, e_{ind}, 1)$ 
24:         $N_w^-[adj\_ind] \leftarrow (v, 0, e_{ind})$ 
25:      else
26:         $w\_rev \leftarrow \bar{w}$ 
27:         $e_{ind\_rev} \leftarrow \overline{e_{ind}}$ 
28:         $adj\_ind \leftarrow get\_index(N_{w\_rev}^+, e_{ind\_rev}, 1)$ 
29:         $N_{w\_rev}^+[adj\_ind] \leftarrow (v, 1, e_{ind\_rev})$ 

```

Algorithm 6 Delete a vertex

```

1: function BG_DELETE_VERTEX( $G, v$ )
2:   for  $(w, e_{ind}) \in N_v$  do
3:      $adj\_ind \leftarrow \text{get\_index}(N_w, e_{ind}, 1)$ 
4:     if  $adj\_ind = |N_w| - 1$  then
5:        $\triangleright$  Just delete the last element
6:        $N_w.\text{pop}()$ 
7:     else
8:        $\triangleright$  Replace the edge by the last in the neighbour list
9:        $N_w[adj\_ind] \leftarrow N_w.\text{pop}()$ 
10:   $\text{delete}(N_v)$ 
11:   $\triangleright$  Delete the whole vertex
12:  if  $v = |N_V| - 1$  then
13:     $\triangleright$  It is the last, just pop it
14:     $N_V.\text{pop}()$ 
15:  else
16:     $\triangleright$  Replace it by the last
17:     $N_v \leftarrow N_V.\text{pop}()$ 
18:     $\triangleright$  Update the vertex index
19:    for  $(w, e_{ind}) \in N_v$  do
20:       $adj\_ind \leftarrow \text{get\_index}(N_w, e_{ind}, 1)$ 
21:       $N_w[adj\_ind] \leftarrow (v, e_{ind})$ 
22:      if  $w > v$  then
23:         $\triangleright$  The last (the greatest) identifier becomes a fewer and breaks
24:           $\triangleright$  the identifier order
25:           $E_{attr}[e_{ind}] \leftarrow (E_{attr}[e_{ind}][0], 1 - E_{attr}[e_{ind}][1])$ 

```

Require: Graph $G = (V, E)$, edge $(u, v) \in E$ (with their orientation $(u_{or}, v_{or}) \in \{0; 1\}^2$ if necessary), edge index e_{ind} .

Ensure: $|N_u^+ \setminus edge| = |N_u^+| - 1$ and $|N_v^- \setminus edge| = |N_v^-| - 1$.

```

1: function DGS_DELETE_EDGE( $G, u, v, e_{ind}$ )
2:   ▷ Remove  $v$  from  $u$ 's successors                                ◁
3:    $adj\_ind \leftarrow \text{get\_index}(N_u^+, e_{ind}, 1)$ 
4:   if  $adj\_ind = |N_u^+| - 1$  then
5:     ▷ Just delete the last element                                ◁
6:      $N_u^+.\text{pop}()$ 
7:   else
8:     ▷ Replace the edge by the last in the neighbour list        ◁
9:      $N_u^+[adj\_ind] \leftarrow N_u^+.\text{pop}()$ 
10:  ▷ Remove  $u$  from  $v$ 's predecessors.                               ◁
11:   $v\_rev \leftarrow \bar{v}$ 
12:   $adj\_ind \leftarrow \text{get\_index}(N_{v\_rev}^+, e_{ind}, 1)$ 
13:  if  $adj\_ind = |N_{v\_rev}^+| - 1$  then
14:    ▷ Just delete the last element                                ◁
15:     $N_{v\_rev}^+.\text{pop}()$ 
16:  else
17:    ▷ Replace the edge by the last in the neighbour list        ◁
18:     $N_{v\_rev}^+[adj\_ind] \leftarrow N_{v\_rev}^+.\text{pop}()$ 
19:   $card\_edges \leftarrow card\_edges - 2$ 

```

```

1: function DGF_DELETE_EDGE( $G, u, u_{or}, v, v_{or}, e_{ind}$ )
2:   ▷ Remove  $v$  from  $u$ 's successors ◁
3:   if  $u_{or} = 0$  then
4:     |  $list\_succs \leftarrow N_u^+$ 
5:     |  $adj\_ind \leftarrow get\_index(list\_succs, e_{ind}, 2)$ 
6:   else
7:     |  $list\_succs \leftarrow N_u^-$ 
8:     |  $adj\_ind \leftarrow get\_index(list\_succs, \overline{e_{ind}}, 2)$ 
9:   if  $adj\_ind = |list\_succs| - 1$  then
10:    | ▷ Just delete the last element ◁
11:    |  $list\_succs.pop()$ 
12:   else
13:    | ▷ Replace the edge by the last in the neighbour list ◁
14:    |  $list\_succs[adj\_ind] \leftarrow list\_succs.pop()$ 
15:   ▷ Remove  $u$  from  $v$ 's predecessors. ◁
16:   if  $v_{or} = 0$  then
17:     |  $list\_preds \leftarrow N_v^-$ 
18:     |  $adj\_ind \leftarrow get\_index(list\_preds, e_{ind}, 2)$ 
19:   else
20:     |  $list\_preds \leftarrow N_v^+$ 
21:     |  $adj\_ind \leftarrow get\_index(list\_preds, \overline{e_{ind}}, 2)$ 
22:   if  $adj\_ind = |list\_preds| - 1$  then
23:    | ▷ Just delete the last element ◁
24:    |  $list\_preds.pop()$ 
25:   else
26:    | ▷ Replace the edge by the last in the neighbour list ◁
27:    |  $list\_preds[adj\_ind] \leftarrow list\_preds.pop()$ 
28:    $card\_edges \leftarrow card\_edges - 2$ 

```

Algorithm 7 Delete an edge

```

1: function BG_DELETE_EDGE( $G, u, u_{or}, v, v_{or}, e_{ind}$ )
2:    $e'_{ind} \leftarrow e_{ind} \div 2$   $\triangleright$  Euclidian division
3:    $\triangleright$  Remove  $v$  from  $u$ 's neighbours.  $\triangleleft$ 
4:    $adj\_ind \leftarrow \text{get\_index}(N_u, e'_{ind}, 1)$ 
5:   if  $adj\_ind = |N_u| - 1$  then
6:      $\triangleright$  Just delete the last element  $\triangleleft$ 
7:      $N_u.\text{pop}()$ 
8:   else
9:      $\triangleright$  Replace the edge by the last in the neighbour list  $\triangleleft$ 
10:     $N_u[adj\_ind] \leftarrow N_u.\text{pop}()$ 
11:    $\triangleright$  Remove  $u$  from  $v$ 's neighbours.  $\triangleleft$ 
12:    $adj\_ind \leftarrow \text{get\_index}(N_v, e'_{ind}, 1)$ 
13:   if  $adj\_ind = |N_v| - 1$  then
14:      $\triangleright$  Just delete the last element  $\triangleleft$ 
15:      $N_v.\text{pop}()$ 
16:   else
17:      $\triangleright$  Replace the edge by the last in the neighbour list  $\triangleleft$ 
18:      $N_v[adj\_ind] \leftarrow N_v.\text{pop}()$ 
19:    $card\_edges \leftarrow card\_edges - 1$ 

```

Algorithm 8 Find place of edge index in the neighbour list. Cost: worst $3 \times |list|$, best 3, average $3 \times \left\lceil \frac{|list|}{2} \right\rceil$

Require: List of tuple $list$, edge index e_{ind} , index t_{ind} of the place of edge index in the tuple contained in $list$. The edge index must be in a tuple.

Ensure: Returns the index of the tuple containing e_{ind} in $list$.

```

1: function GET_INDEX( $list, e_{ind}, t_{ind}$ )
2:    $list_{ind} \leftarrow 0$ 
3:   while  $list[list_{ind}][t_{ind}] \neq e_{ind}$  and  $list_{ind} < |list| - 1$  do
4:      $list_{ind} \leftarrow list_{ind} + 1$ 
5:   return  $list_{ind}$ 

```

Acronyms

This document is incomplete. The external file associated with the glossary ‘abbreviations’ (which should be called `revsymg_main.gls-abr`) hasn’t been created.

Check the contents of the file `revsymg_main.glo-abr`. If it’s empty, that means you haven’t indexed any of your entries in this glossary (using commands like `\gls` or `\glsadd`) so this list can’t be generated. If the file isn’t empty, the document build process hasn’t been completed.

Try one of the following:

- Add `automake` to your package option list when you load `glossaries-extra.sty`. For example:

```
\usepackage[automake]{glossaries-extra}
```

- Run the external (Lua) application:

```
makeglossaries-lite.lua "revsymg_main"
```

- Run the external (Perl) application:

```
makeglossaries "revsymg_main"
```

Then rerun \LaTeX on this document.

This message will be removed once the problem has been fixed.

Symbols

This document is incomplete. The external file associated with the glossary ‘symbols’ (which should be called `revsymg_main.sls`) hasn’t been created.

Check the contents of the file `revsymg_main.slo`. If it’s empty, that means you haven’t indexed any of your entries in this glossary (using commands like `\gls` or `\glsadd`) so this list can’t be generated. If the file isn’t empty, the document build process hasn’t been completed.

Try one of the following:

- Add `automake` to your package option list when you load `glossaries-extra.sty`. For example:

```
\usepackage[automake]{glossaries-extra}
```

- Run the external (Lua) application:

```
makeglossaries-lite.lua "revsymg_main"
```

- Run the external (Perl) application:

```
makeglossaries "revsyng_main"
```

Then rerun \LaTeX on this document.

This message will be removed once the problem has been fixed.

Computational

This document is incomplete. The external file associated with the glossary ‘computational’ (which should be called `revsyng_main.gls-comp`) hasn’t been created.

Check the contents of the file `revsyng_main.glo-comp`. If it’s empty, that means you haven’t indexed any of your entries in this glossary (using commands like `\gls` or `\glsadd`) so this list can’t be generated. If the file isn’t empty, the document build process hasn’t been completed.

Try one of the following:

- Add `automake` to your package option list when you load `glossaries-extra.sty`. For example:

```
\usepackage[automake]{glossaries-extra}
```

- Run the external (Lua) application:

```
makeglossaries-lite.lua "revsyng_main"
```

- Run the external (Perl) application:

```
makeglossaries "revsyng_main"
```

Then rerun \LaTeX on this document.

This message will be removed once the problem has been fixed.

Glossary

This document is incomplete. The external file associated with the glossary ‘main’ (which should be called `revsyng_main.gls`) hasn’t been created.

Check the contents of the file `revsyng_main.glo`. If it’s empty, that means you haven’t indexed any of your entries in this glossary (using commands like `\gls` or `\glsadd`) so this list can’t be generated. If the file isn’t empty, the document build process hasn’t been completed.

If you don’t want this glossary, add `nomain` to your package option list when you load `glossaries-extra.sty`. For example:

`\usepackage[nomain]{glossaries-extra}`

Try one of the following:

- Add `automake` to your package option list when you load `glossaries-extra.sty`. For example:

```
\usepackage[automake]{glossaries-extra}
```

- Run the external (Lua) application:

```
makeglossaries-lite.lua "revsyng_main"
```

- Run the external (Perl) application:

```
makeglossaries "revsyng_main"
```

Then rerun \LaTeX on this document.

This message will be removed once the problem has been fixed.